



OFFICE OF THE MANAGING DIRECTOR
ASSAM MEDICAL SERVICE CORPORATION LIMITED
SAIKIA COMMERCIAL COMPLEX, SRINAGAR PATH, CHRISTIANBASTI,
G.S ROAD, GUWHATI 781005

No: AMSCL-17/PROC/WALK IN COOLER/17-18/ 97-P

Date 21-7-2018

CORRIGENDUM NO. 2

This is with reference to TENDER NO: No: AMSCL-17/PROC/WALK IN COOLER/17-18/54-P, Date:21-05-2018 & Corrigendum No: AMSCL-17/PROC/WALK IN COOLER/17-18/54-P, Date:21-05-2018 for “**SUPPLY & INSTALLATION OF WALK IN COOLER**”.

Some amendments are incorporated which must be considered prior to submission of the Tender.

1. TECHNICAL SPECIFICATIONS

A. Pt. 3. Insulation: Condensing unit: may be read as Condensing unit must have air cooled condenser and should comprise scroll type hermetically sealed compressor. Condenser coil should be copper coil and the compressor to have internal overload protector. Sound pressure level @ 1 m 60 Db (A). Referent used to be Eco friendly CFC free R404A. Material of the body should be GI powder coated for rust free.

Condensing unit to comprise compressor, forced air cooled fin and tube condenser to carry full charge, filter/dryer with flare connections, service and isolating top valves and suction line accumulator with oil trap.

B. Pt. 3. Insulation: may be read as Maximum permissible door size is 3 ft (w) x 7 ft (H).

C. Pt. 3. Insulation: may be read as 3rd layer aluminum checker plate to be 1.2 mm (min) thickness with 6 mm Marine Ply (water proof).

D. Pt. C. Fabrication: Hold over time may be read as: it depends on round the clock availability of electricity and the number of times the doors are opened. This clause proposed to eliminate from the tender. 8 hour hold over time only with full load condition without door opening. The insulation should be suitable for maintaining 8 hours hold over time at 43 degree °C ambient temperature.

E. Pt.3. Insulation: Each entrance door shall have an incandescent vapor-proof light mounted on the interior of the door section is hereby removed, however LED light will be required only inside the Cold Room.

F. Pt.3. Insulation: The door dimensions may be read as 860 mm x 1960 mm X 80 mm thick x 1 No. PCGI/PCGI.
The door should be mounted with tungsten filament lighting with an external switch and pilot light.

- G. Pt. 3. Insulation:** Refrigeration system may be read as (100% standby) should be air cooled refrigeration units, plug in type/split type/unitary system automatic defrosting , CFC free refrigerant, Tropicalized units suitable for ambient temperature upto 43 degree C.
- H. Pt.3. Insulation:** Digital thermometer may be read as The provision of display of room temperature by digital thermometer of 4 digits LCD/LED display.
- I. Pt.3. Insulation:** Storage conditions may be read as Storage conditions to be maintained at +4 degree C ($\pm 2^{\circ}\text{C}$).

2. Pt. No. 2 **IMPORTANT NOTES and MADATE CREDENTIAL-Pt. No. (C)**

Supply and installation should be supported by 2 years warranty and 8 years Comprehensive Maintenance Contract.

3. Committee recommends that total warranty of 5 years followed by a CMC of 5 years i.e a total 10 years service required for the Walk in cooler. Hence in view of immediate repair/ renovation on any breakdown in future, it is mandate that the bidder or his parent manufacturing company should have authorized service center in the state of Assam or required to establish the service center immediately within 15 days (under taking in an non judicial stamp paper must be submitted & uploaded with the bid), after awarding the service contract.

4. The Annexure XIII read as Annexure XIII-Rev

ANNEXURE XIII-Rev
Financial Sheet 1

(To be uploaded only as .pdf document in the financial folder. Hardcopy of the same will not be accepted)

SI No	Name of the Items	Basic Price Per Unit/Per set (in Rupees)	Applicable GST in % (if any)	Applicable GST (in Rs.) (if any)	Total Amount (including GST) (in Rupees)
1	<u>WALK IN COOLER with accessories</u>				
2	Refrigeration Unit (specification mentioned in the Bid document)				
3	Fabrication work (specification mentioned in				

	the Bid document)				
4	Insulation work (specification mentioned in the Bid document)				
5	Automatic Voltage Stabilizer of 10 KVA				
6	Panel Board with Earthing				
7	CMC for 5 years effective from post warranty period.				

Last Date and Time of submission of Tender Document will be extended till 26-07-2018 (up to 2:00 PM)

All other terms and conditions of the above referred tender shall remain unchanged.

Sd/-

Managing Director, AMSCL, Assam